

Semi Detached House built 1996

Total Building Area (m2): 83

	BER Rating	Energy Value	Potential Energy Savings	Total Annual Space Heating Demand	Heating costs per year [1]
		(kWh/m2/yr)	€	kWh/yr	€/yr
Dwelling Current Condition	C3	221.37	-	18,374	€3,123.53
Dwelling Post Works	A3	58.54	€2,443.30	4,859	€680.23
CO2 Savings per year		4.32 Tonnes			
Equivalent Planted Trees		308 Trees			

Item	Recommendation	kWh/m ² /yr	BER	MEDIAN Cost Nett Grant [2]
Roof Insulation	Install 200mm of attic insulation	199.71	C2	€700
New windows with a uvalue of 1.2 New Door with a uvalue of 1.4	New windows with a u-value of 1.2 and a Solar Transmittance of 0.6 including roof windows New door with a U-value of 1.4	185	C2	€4,500
Blocking of Chimneys & Vents	Install closable vents in all bedrooms if not already installed and block all others. Remove open fires and stoves and block chimneys. Draught strip all attic hatches.	180	B3	€800
Heating system and Controls	Install full time and temperature controls with 3 zonestwo heating and one HW. Install and air to water HP with a Seasonal Space Heating Efficiency, η_s / SCOP/A of 127 minimum and Water Heating Efficiency, η_{wh} 125 minimum. HW cylinder taken as 200L with a Declared loss of 1.5 KWH/day. As part of this upgrade, we have allowed for the blocking up of any and all open fires.	58.5	A3	€10,000
Total Cost €				€16,000
Simple Payback (Years)				6.5

[1] Assumes (and this is critical) that the electrical load for the Heat Pump is shifted as much as possible to cheaper rates on a Smart meter plan

[2] These costs are net of SEAI and are based on a SEAI survey of actual retrofit works carried out by certified contractors in 2025

The house pictured is not the actual home surveyed, but it has the same characteristics